

– Assorted C.C Blocks (including block at Key) to be placed at Key & to be dumped below working WL @ 47 m³ / m (Excluding Void)

| | |
|-----------------------|------|
| 500 x 500 x 500 ----- | 60 % |
| 400 x 400 x 400 ----- | 40 % |

[See Details "X"](#)

See Details "Z"

—250 Kg Sand Filled Geo-bag to be dumped below working WL @ 50 m³/m

Working WL 5.00 m (PWD)

15-18cm dia & 6.00m long
hard wood bullah @ 1.20m C/C

1.50 m →
63.00 m →

ELEVATION

Geo-Bag: Placing/ Dumping @ 50 m³/m

DISTANCE

SECTION XI-XI
(Limit of work from A1 to B1)

a) For Details "X", "Y" & "Z" See Sheet No. 27 of 33

| | | | | "Protection of Talbaria area of Mijpur Upazila & Kamorkandi area of Shelaibah Union of Kumarkhali Upazila in Kushtia District from the erosion of Padma River" | | | |
|--------------------------|----------|-----|-----|--|--------------------------------------|--------------------------|--|
| | | | | Design of Protective Work along the R/B of Padma River from KM 6.720 to KM 15.720=9.000 KM at Talbaria, Baruipara and Bahalbaria union, Upazila: Mirpur, District: Kushtia Kushtia WD Division, BWDB, Kushtia. | | | |
| | | | | DETAILS OF U/S END TERMINATION | | | |
| | | | | DESIGNED BY: | RECOMMENDED BY: | | |
| | | | | (SHAMMI AKHTER), SDE CHECKED BY: | (JAKARIA PERVEZ), SE APPROVED BY: | | |
| | | | | (MST. TASMEM JAHAN), EE | (MD. MAHFUZUR RAHMAN), CE, DESIGN | | |
| DATE | PREPARED | CHD | REM | APPROVED | DATE: 00-00-2025 | DWG NO.: DC-5-0000-24/33 | |
| R E V I S I O N S | | | | | | | |